

## End Area Volume Report Wye Track A

Baseline Station	Station Quantities						Mass Ordinate
	Cut			Fill			
	Area	Volume	Adjusted	Area	Volume	Adjusted	
0+00.00	3	0	0	174	0	0	0
1+00.00	12	28	28	45	405	405	-377
2+00.00	195	383	383	0	82	82	-76
3+00.00	433	1163	1163	0	0	0	1087
4+00.00	382	1508	1508	0	1	1	2595
5+00.00	120	929	929	0	1	1	3524
6+00.00	0	223	223	159	295	295	3452
7+00.00	0	0	0	328	901	901	2549
8+00.00	0	0	0	635	1782	1782	767
8+01.35	0	0	0	876	38	38	729
9+00.00	0	0	0	534	2575	2575	-1846
10+00.00	0	0	0	546	2000	2000	-3846
11+00.00	0	0	0	574	2074	2074	-5920
11+27.43	0	0	0	740	668	668	-6588
11+62.88	0	0	0	792	1006	1006	-7594
12+00.00	0	0	0	611	964	964	-8558
12+00.09	0	0	0	846	2	2	-8560
13+00.00	0	0	0	614	2701	2701	-11261
13+27.74	0	0	0	1045	852	852	-12113
13+53.16	0	0	0	1065	993	993	-13106
13+80.16	0	0	0	1074	1070	1070	-14176
14+00.00	0	0	0	539	593	593	-14769
15+00.00	0	0	0	371	1684	1684	-16453
16+00.00	3	6	6	168	998	998	-17441
17+00.00	4	13	13	161	610	610	-18039
18+00.00	5	17	17	139	556	556	-18578
<b>Grand Total</b>		4270	4270		22851	22851	

## End Area Volume Report Wye Track B

Baseline Station	----- Station Quantities -----						Mass Ordinate
	----- Cut -----			----- Fill -----			
	Area	Volume	Adjusted	Area	Volume	Adjusted	
0+00.00	214	0	0	0	0	0	0
1+00.00	211	787	787	0	0	0	787
2+00.00	83	544	544	8	14	14	1317
3+00.00	79	299	299	0	14	14	1602
4+00.00	33	207	207	15	27	27	1781
5+00.00	0	61	61	116	242	242	1601
6+00.00	0	0	0	158	506	506	1095
7+00.00	0	0	0	234	726	726	369
8+00.00	0	0	0	209	821	821	-452
8+16.62	0	0	0	217	131	131	-583
9+00.00	0	0	0	172	600	600	-1183
10+00.00	0	0	0	149	593	593	-1776
11+00.00	3	6	6	114	486	486	-2257
12+00.00	5	15	15	35	276	276	-2518
<b>Grand Total</b>		<b>1919</b>	<b>1919</b>		<b>4436</b>	<b>4436</b>	

## End Area Volume Report Track C/D

Baseline Station	----- Station Quantities -----							Mass Ordinate
	----- Cut -----			----- Fill -----				
	Area	Volume	Adjusted	Area	Volume	Adjusted		
0+00.00	96	0	0	4	0	0	0	
1+00.00	121	402	402	2	11	11	391	
2+00.00	148	499	499	8	20	20	869	
3+00.00	238	715	715	6	27	27	1557	
4+00.00	310	1014	1014	5	20	20	2550	
5+00.00	346	1215	1215	3	15	15	3750	
6+00.00	409	1398	1398	3	11	11	5137	
7+00.00	454	1597	1597	3	10	10	6724	
8+00.00	489	1746	1746	2	9	9	8461	
9+00.00	507	1844	1844	2	8	8	10297	
10+00.00	497	1859	1859	3	9	9	12147	
11+00.00	482	1813	1813	3	10	10	13949	
12+00.00	467	1756	1756	2	9	9	15697	
13+00.00	481	1756	1756	5	13	13	17439	
14+00.00	463	1748	1748	10	28	28	19160	
15+00.00	418	1631	1631	13	43	43	20748	
16+00.00	401	1516	1516	23	66	66	22199	
17+00.00	324	1343	1343	22	83	83	23459	
18+00.00	269	1098	1098	21	80	80	24476	
19+00.00	250	961	961	15	68	68	25370	
20+00.00	206	845	845	23	71	71	26143	
21+00.00	197	746	746	26	90	90	26799	
22+00.00	156	653	653	20	84	84	27368	
23+00.00	139	546	546	16	66	66	27847	

24+00.00	148	531	531	13	53	53	28324
25+00.00	128	511	511	7	36	36	28799
26+00.00	115	449	449	3	17	17	29232
27+00.00	76	353	353	3	11	11	29574
28+00.00	59	249	249	5	15	15	29808
29+00.00	12	130	130	37	77	77	29861
30+00.00	14	46	46	32	127	127	29780
31+00.00	17	57	57	40	133	133	29705
32+00.00	19	66	66	51	169	169	29602
33+00.00	14	60	60	66	217	217	29444
34+00.00	9	42	42	89	287	287	29199
34+82.51	17	40	40	153	369	369	28870
34+90.39	16	5	5	130	41	41	28833
34+97.99	12	4	4	113	34	34	28803
35+00.00	10	1	1	79	7	7	28797
36+00.00	17	49	49	64	265	265	28581
37+00.00	14	56	56	57	224	224	28413
38+00.00	16	55	55	60	216	216	28251
39+00.00	34	92	92	25	156	156	28187
40+00.00	30	117	117	27	95	95	28209
41+00.00	52	150	150	20	87	87	28272
42+00.00	66	218	218	24	82	82	28408
43+00.00	50	214	214	76	184	184	28438
44+00.00	15	120	120	177	467	467	28091
45+00.00	2	32	32	274	835	835	27288
46+00.00	4	11	11	253	975	975	26324
47+00.00	8	23	23	169	780	780	25566
48+00.00	11	35	35	124	542	542	25059
49+00.00	2	23	23	159	522	522	24560
Grand Total		32440	32440		7874	7874	

## End Area Volume Report Loop Track E

Baseline Station	Station Quantities							Miss Ordnate
	Cut			Fill				
	Area	Volume	Adjusted	Area	Volume	Adjusted		
0+00.00	6	0	0	91	0	0	0	
1+00.00	5	20	20	98	339	339	320	
2+00.00	6	20	20	90	337	337	637	
3+00.00	73	146	146	84	322	322	813	
4+00.00	103	326	326	68	282	282	769	
5+00.00	149	468	468	64	245	245	546	
6+00.00	192	631	631	63	236	236	151	
7+00.00	237	795	795	55	219	219	424	
8+00.00	306	1007	1007	39	174	174	1256	
9+00.00	329	1176	1176	45	156	156	2276	
10+00.00	445	1433	1433	39	157	157	3552	
11+00.00	307	1393	1393	0	73	73	4872	
12+00.00	260	1050	1050	0	0	0	5922	
13+00.00	170	795	795	0	0	0	6717	
14+00.00	50	406	406	38	71	71	7053	
15+00.00	31	150	150	49	161	161	7042	
16+00.00	32	117	117	6	101	101	7058	
17+00.00	29	114	114	21	50	50	7121	
18+00.00	19	89	89	18	72	72	7139	
19+00.00	23	77	77	23	76	76	7139	
20+00.00	21	81	81	53	141	141	7079	
20+12.54	14	8	8	76	29	29	7058	
21+00.00	3	28	28	116	308	308	6778	
22+00.00	13	31	31	199	583	583	6226	
23+00.00	33	85	85	69	495	495	5816	
24+00.00	78	206	206	0	127	127	5895	
25+00.00	98	327	327	0	0	0	6222	
26+00.00	79	327	327	0	0	0	6549	
27+00.00	2	149	149	104	193	193	6505	
28+00.00	26	51	51	19	229	229	6328	
29+00.00	31	104	104	15	64	64	6368	
30+00.00	4	63	63	72	161	161	6271	
31+00.00	0	7	7	118	351	351	5927	
31+18.91	26	9	9	154	95	95	5841	
31+25.09	1	3	3	239	45	45	5799	
31+31.26	0	0	0	271	58	58	5741	
32+00.00	174	221	221	0	344	344	5618	
33+00.00	493	1235	1235	0	0	0	6853	
34+00.00	738	2279	2279	0	0	0	9132	
35+00.00	617	2508	2508	0	0	0	11641	
36+00.00	456	1986	1986	0	0	0	13627	
37+00.00	196	1206	1206	0	0	0	14833	
38+00.00	90	528	528	0	0	0	15361	
39+00.00	25	211	211	27	49	49	15523	
40+00.00	13	70	70	80	197	197	15396	
41+00.00	24	69	69	82	300	300	15164	
42+00.00	26	92	92	115	366	366	14890	
Grand Total		22097	22097		7206	7206		

Baseline Station	Station Quantities							Miss Ordnate
	Cut			Fill				
	Area	Volume	Adjusted	Area	Volume	Adjusted		
43+00.00	9	0	0	118	0	0	0	
43+26.87	18	14	14	160	139	139	125	
43+32.82	25	5	5	132	32	32	153	
44+00.00	15	50	50	95	282	282	384	
45+00.00	21	67	67	59	284	284	602	
46+00.00	29	92	92	45	193	193	702	
47+00.00	79	199	199	0	84	84	588	
48+00.00	257	621	621	0	0	0	33	
49+00.00	274	983	983	0	0	0	1016	
50+00.00	113	718	718	0	0	0	1734	
51+00.00	37	279	279	10	19	19	1994	
51+46.07	10	40	40	50	52	52	1982	
52+00.00	8	18	18	75	125	125	1875	
52+21.48	21	12	12	147	88	88	1798	
53+00.00	7	41	41	81	331	331	1508	
54+00.00	7	26	26	86	309	309	1224	
55+00.00	0	13	13	119	378	378	859	
56+00.00	0	1	1	128	457	457	404	
57+00.00	0	1	1	100	422	422	18	
58+00.00	4	8	8	70	314	314	323	
58+43.93	0	3	3	87	128	128	448	
59+00.00	1	1	1	96	190	190	637	
60+00.00	10	20	20	47	264	264	880	
61+00.00	25	66	66	41	162	162	977	
62+00.00	45	129	129	42	153	153	1001	
63+00.00	35	146	146	40	151	151	1006	
64+00.00	42	141	141	43	154	154	1019	
65+00.00	47	163	163	47	167	167	1022	
66+00.00	54	186	186	41	164	164	1000	
67+00.00	56	203	203	43	156	156	953	
67+98.54	57	206	206	27	127	127	874	
68+00.00	50	3	3	36	2	2	873	
69+00.00	66	216	216	10	84	84	741	
70+00.00	68	249	249	17	50	50	542	
71+00.00	97	306	306	5	40	40	276	
72+00.00	158	472	472	0	9	9	187	
73+00.00	192	647	647	0	0	0	834	
74+00.00	210	743	743	0	0	0	1578	
75+00.00	211	779	779	0	0	0	2357	
76+00.00	128	628	628	0	0	0	2985	
77+00.00	172	555	555	0	0	0	3540	
78+00.00	225	734	734	0	0	0	4274	
Grand Total		9784	9784		5510	5510		